

6070418

15-009-30398-00-00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

C-5W, SEC. *29*, T. *16* S, R. *11* W. *6*

TECHNICIAN'S PLUGGING REPORT

Operator License # *4519*

1320 feet from S section line

3960 feet from E section line

Lease Name *Joseph* Well # *13- INJ.*

County *Barber* 99.13

Well Total Depth *3050* feet

Conductor Pipe: Size *0* feet

Surface Casing: Size *8 5/8"* feet *170*

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor *Halliburton Cementing Inc* License Number _____

Address *Great Bend, Kans.*

Company to plug at: Hour: *10:10 AM* Day: *20th* Month: *June* Year: *1985*

Plugging proposal received from *Dave Lazure*

(company name) *Gulf Chevron Oil Co* (phone) _____

were: *8 5/8" - 170 FE 50. cuw w/ 175^{SS} emt, 4 1/2" log set @ 2050 FE w/ 150^{SS} emt.*

Stage collar @ 832 FE cuw w/ 150^{SS} emt, emt did not circulate.

Perts @ 2982^{FE} to 2981^{FE}

Order 400^{SS} Class A. Cement. 25^{SS} Gel - No Cel. - And Vulls.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: _____ Day: *20th* Month: *June* Year: *1985*

ACTUAL PLUGGING REPORT *Ordered 400^{SS} Class A. Cement, 25^{SS} Gel, No Cel & Vulls.*

Ran tubing to 2840^{FE} loaded hole with Gel.

@ 2840^{FE} spotted w/ 150^{SS} emt, @ 2793^{FE} Circulated cement

to surface w/ 230^{SS} emt, filled 4 1/2" log to cellar w/ 19^{SS} emt.

Pressured annulus with cement w/ 38^{SS} emt, shut in @ 200 Psig

Cemented by Halliburton, emt

Remarks: *12-2-85*

(If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)
DATE *DEC 14 1985* DEC 2 1985 Signed *Marvin Schmidt* (TECHNICIAN)

WICHITA, KANSAS CONSERVATION DIVISION
Wichita, Kansas

INV. NO. *11418* FORM CP-2/3 Rev. 01-84