

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-01383-00-00
Spot: NWSESWSE Sec/Twnshp/Rgc: 30-23S-15W
641 feet from S Section Line, 1901 feet from E Section Line
Lease Name: HALL, DG Well #: 1
County: PAWNEE Total Vertical Depth: 3099 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	3099	1116	WITH 700 SX CMT
SURF	8.625	154		WITH 170 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/21/2016 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: RANDY GNIEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: BOTTOM PLUG PUMP 25 SX CMT WITH HULLS. PUMP 15 SX GEL& 50 SX CMT AT 980'. TAG PLUG. REPEAT IF NEEDED. CIRCULATE TO SURFACE AT 300'. TOP OFF AS NEEDED.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 11:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

12/2/16: SQUEEZE PERFS WITH 25 SX CMT & 50# HULLS. 12/21/16: COULD NOT TAG CMT. PUMP 25 SX CMT WITH 150# HULLS & 4% CC TO 1100'. WOC ONE HOUR. TAG CMT AT 1150'. TAG PLUG AT 1150'. 12/22/16: CUT TBG AT 1116'. PULL UP TO 990' & PUMP 15 SX GEL FOLLOWED BY 50 SX CMT. PULL TBG TO 300' & PUMP 75 SX CMT TO SURFACE. PULL TBG & TOP OFF WITH 5 SX CMT. HOLE STANDING FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2587	2595		

Remarks: USED 60/40 POZMIX 4% GEL 3-4% CC BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

SA

RECEIVED
DEC 28 2016
KCC DODGE CITY



INVOICED
JAN 03 2017