

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-01462-00-01
Spot: E2NESE Sec/Twnshp/Rge: 34-19S-10W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: DALTON Well #: 3
County: RICE Total Vertical Depth: 3288 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3286		175 SX
SURF	10.75	202		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TODD A. BROWN Company: _____ Phone: (785) 445-6270

Proposed Plugging Method: Set CIBP 50' above Arbuckle perforations (CIBP 3234' setting depth) and cap with 2 sx cement. Set tubing @ 1250' and pump 35 sx, pull tubing to 875' and pump 35 sx. Pull tubing to 3252' and circulate cement to surface. Cement type: Common cement w/additives as recommended.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2016 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, pull tubing. Set CIBP @ 3234' and cap with 2 sx's cement. Perforate at 1250', 875' and 252'. Run tubing to 1250' and pump 35 sx's common cement with 3% CC. Pull tubing to 875' and wait 1hr. Tagged cement at 918'. Pump 35 sx's common cement with 3% CC at 875'. Pull tubing to 252' and circulate cement to surface. Pull tubing out and top off.

Perfs:

Top	Bot	Thru	Comments
3286	3288		
3284	3286		

Remarks: GEMINI PERF TICKET #2677. QUALITY OILWELL CEMENT #3109.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Form CP-2/3

INVOICED
JAN 03 2017

18