

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-079-20094-00-00  
Spot: S2N2NE Sec/Twnshp/Rgc: 1-24S-2E  
990 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: MCCUNE ESTATE Well #: 4  
County: HARVEY Total Vertical Depth: 2722 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2696		100 SX
SURF	8.625	213		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2016 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: JASON RUCKER Company: RAYMOND OIL COMPANY, INC. Phone: (316) 882-8825

Proposed  
Plugging  
Method:

As directed by the KCC

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2016 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Ran in hole w/ wireline and set CIBP at 2646' Capped w/ 2 sks cement
- 2) Loaded hole, pressured tested casing at 500 psi - held
- 3) Ran in w/ wireline and perforated at 265' w/ 4 shots
- 4) Cut window on surface casing and installed ball valve
- 5) Tied into 4.5" casing and pumped 95 sks 60/40/4% class A cement w/ 2% CaCl and hulls. Circulated cement to surface.

12/22/2015:

- Checked top plug, topped off well w/ 2.5 sks cement

Remarks: CEMENTING COMPLETED BY CONSOLIDATED WELL SERVICES, EL DORADO, KS. TICKET #: 51951

Plugged through: CSG

District: 02

Signed Jonathan Hill

(TECHNICIAN)

INVOICED  
JAN 03 2017