

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-20092-00-00
Spot: NENENWNE Sec/Twnshp/Rge: 1-24S-2E
5076 feet from S Section Line, 1575 feet from E Section Line
Lease Name: MCCUNE ESTATE Well #: 3
County: HARVEY Total Vertical Depth: 2722 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2718		100 SX
SURF	8.625	209		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2016 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JASON RUCKER Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: As directed by the KCC.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 11:30 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Ran in hole w/ wireline and set CIBP at 2647' and capped w/ 2 sks cement
- 2) Loaded hole, pressured tested casing at 500 psi - held
- 3) Ran in w/ wireline and perforated at 260' w/ 4 shots
- 4) Cut window on surface casing and installed ball valve
- 5) Tied in 5.5" casing and pumped 120 sks 60/40/4% class A cement w/ 2% CaCl. Cement circulated to surface

Remarks: CEMENTING COMPLETED BY CONSOLIDATED WELL SERVICES, EL DORADO, KS. TICKET #: 51952

Plugged through: CSG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

Form CP-2/3

INVOICED

JAN 03 2017