

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21619-00-02
Spot: E2E2SE Sec/Twnshp/Rge: 15-7S-17W
1452 feet from S Section Line, 356 feet from E Section Line
Lease Name: FENTON OWWO Well #: 1
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 32698
Op Name: RALEIGH E FENTON DBA ENF PRODU
Address: 2360 J ROAD
STOCKTON, KS 67669

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3377		
SURF	8.625	1105		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2016 2:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-7218

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2016 5:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 5 1/2" casing at 1050'. Ran tubing to 3350' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2350' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 230 sx cement to bring 5 1/2' casing to surface and circulate fluid from annulus. Pulled all tubing. Hooked to 5 1/2" casing and pumped 50 sx cement to circulate annulus to surface and top off 5 1/2" casing.

GPS: 39.44130N -099.19473W

Perfs:

KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: GLOBAL TICKET # 2745

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

NOV 21 2016

INVOICED
JAN 03 2017

Form CP-2/3