

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-30368-00-00  
Spot: NENESW Sec/Twnshp/Rge: 18-16S-14W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: HERMAN Well #: 1  
County: BARTON Total Vertical Depth: 3429 feet

Operator License No.: 30275  
Op Name: REDDIG, ROGER L. DBA CLOVER OIL  
Address: PO BOX 173  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3402		425 SX
SURF	8.625	300		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/06/2016 10:00 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: ROGER L. REDDIG Company: REDDIG, ROGER L. DBA CLOVER Phone: (785) 483-3085

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/06/2016 5:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 930' and 300'. Ran tubing to 3200' and pumped 120 sx cement w/200 # hulls. Pulled tubing to 2000' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 100 sx cement. Pulled tubing to 300'. Circulated cement to surface with 30 sx cement. Tied to backside and pumped 20 sx cement. Started to pressure up and blew out fitting on other side of head. Topped off casing with 30 sx cement.  
12/08/2016- Topped off with 40 sx cement.

GPS: 38.65856 -098.91410

Perfs:

Top	Bot	Thru	Comments
3138	3368		

KCC WICHITA  
DEC 19 2016  
RECEIVED

Remarks: GLOBAL SERVICES

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

DEC 09 2016

INVOICED

Form CP-2/3

JAN 03 2017