

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20656-00-00
Spot: W2W2NE Sec/Twnshp/Rge: 11-6S-33W
1320 feet from N Section Line, 2310 feet from E Section Line
Lease Name: FRANKLIN Well #: 1
County: THOMAS Total Vertical Depth: 4580 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4574		250 SX
SURF	8.625	287		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2016 10:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. DBA Phone: (316) 691-9500

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
8 5/8" surface casing set at 287' w/165 sx cement.
4 1/2" production casing set at 4574' w/250 sx cement.
TD 4580', PBD 4508'.
Stage collar set at 2678' w/700 sx cement. Cement did not circulate. Pumped 200 sx cement down annulus for a total of 900 sx cement.
Perforations: 4346' - 4352', 4145' - 4154', 4060' - 4062'. Pawnee and LKC formations.
Squeezed at 3975' - 4124' w/100 sx common cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2016 10:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Tubing was un-screwed and had dropped to bottom of well. Operator fished tubing from well and recovered corkscrewed string. Fluid level 129 joints from surface. Top down plug requested by operator's representative.
Connected to 4 1/2" production casing and pumped 305 sx cement w/600 # hulls. Casing full. Maximum pressure 1000 psi. Cement visible in 8 5/8" annulus.

GPS: 39.55016N -100.96886W

Perfs:

Top	Bot	Thru	Comments
4346	4352		
4145	4154		
4060	4062		

KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: GLOBAL OILFIELD SERVICES LLC CEMENT TICKET # 2175

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

DEC 05 2016

INVOICED
JAN 03 2017