

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20451-01-00  
Spot: N2N2NENE Sec/Twnshp/Rge: 24-26S-30W  
201 feet from N Section Line, 659 feet from E Section Line  
Lease Name: BLEUMER 2630 Well #: 3-13H  
County: GRAY Total Vertical Depth: 5018 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5700		WITH 15 SX CMT
COND	20	120		
PROD	7	5010	2008	WITH 365 SX CMT
SURF	9.625	1572		WITH 747 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2016 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TIH w/7" tbg and set CIBP at 5700'. Circ hole w/mud & cap w/15 sks cement. Weld on 7" pullsub. Pull 7" slips, NU 11" BOP. Cut & pull free pipe. Spot following cement plugs: a) @ 1620' spot 100 sks Class C Cement. b) @ 950' spot 50 sks Cement c) @ 64' to 4' spot 20 sks Cement. RDMOSU Cut & Cap Well. Dig up rig anchors

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/06/2016 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5700' WITH 15 SX CMT. CIRCULATE HOLE WITH MUD. 1ST PLUG AT 1620' WITH 100 SX CMT. 2ND PLUG AT 775' WITH 50 SX CMT. 3RD PLUG AT 64' TO 4' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5976	6903		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 7210'.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
SA

(TECHNICIAN)

RECEIVED  
DEC 15 2016  
KCC DODGE CITY

*MD*

Form CP-2/3

INVOICED

JAN 03 2017