

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-20793-00-00
Spot: N2NWSWSE Sec/Twnshp/Rge: 19-18S-7E
1195 feet from S Section Line, 2970 feet from W Section Line
Lease Name: LIPS Well #: 5-19
County: CHASE Total Vertical Depth: 1378 feet

Operator License No.: 5192 String Size Depth (ft) Pulled (ft) Comments
Op Name: SHAWMAR OIL & GAS CO., INC. PROD 4.5 1365 170 SX
Address: 1116 E MAIN PO BOX 9 SURF 8.625 204 120 SX
MARION, KS 66861

Well Type: OG UIC Docket No: Date/Time to Plug: 12/13/2016 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BENNY KEY Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 381-1023

Proposed Plugging Method: Sand back 50' above perfs and place 4 sacks cement with dump bailer. Swab 4.5' down to 250', set bridge and dump cement to top of 4.5' casing.

Plugging Proposal Received By: JERRY SPARLING Witness Type: PARTIAL
Date/Time Plugging Completed: 12/20/2016 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

12/14/2016:
- Sanded back to 1206' and capped w/ 4 sks Class A cement

Top	Bot	Thru	Comments
1301	1311		

12/15/2016:

- 1) Rigged up swab cups, swabbed down to 265', mixed and dumped 12 sks cement
- 2) Dug out well -- no cement at surface. Ran in tagline on back side of 4.5" casing, no cement encountered 200'+.

12/20/2016:

- 1) Ran in 1" tubing on backside of 4.5" casing to 250'.
- 2) Pumped 50 sks 60/40/4% Class A cement w/ 2% CaCl and 50 lbs hulls, circulated cement to surface.
- 3) Ran in 1" tubing inside 4.5" casing, tagged plug at 75' w/ no fluid on top. Pulled 1" out
- 4) Ran in poly-line and pumped 25 sks cement. Cemented to surface and topped off backside

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET#: 51948

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

INVOICED ^{Form CP-2/3}
JAN 03 2017