

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20705-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 34-29S-10E
3860 feet from S Section Line, 4657 feet from E Section Line
Lease Name: DUNKLEBERGER Well #: 30
County: ELK Total Vertical Depth: 1484 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1483		0 SX
SURF	7	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKINS Company: _____ Phone: (620) 374-2000

Proposed Plugging Method: There is information on surface casing amount or cementing data. Run in to TD with 1" tubing, set 50ft cement plug, pull 1" tubing, perforate wellbore at 1000ft and 500ft, run in with 1" tubing and set 50ft plug at 1000ft, pull o 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 09/28/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1270' gelled hole and spotted 3 sacks plug. Pulled up 800' and spotted 3 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 20 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1300	1320		

RECEIVED
KCC DIST #3
DEC 15 2016
CHANUTE, KS


DS
KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)

INVOICED

JAN 03 2017