

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19234-00-00
Spot: NENWSWSW Sec/Twnshp/Rge: 34-29S-10E
1020 feet from S Section Line, 4955 feet from E Section Line
Lease Name: ELDEN BURKE Well #: 9
County: ELK Total Vertical Depth: 1392 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	1360		0 SX
SURF	8.25	797		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKINS Company: _____ Phone: (620) 374-2000

Proposed Plugging Method: This is old cable tool well with open-hole completion. Only records for well is driller's log from 1937. Run in with 1" tubing to TD, spot 50ft cement plug, pull 1" tubing, perforate at 1000ft and 500ft, run in with 1" tubing and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 09/29/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1386' gelled hole and spotted 15 sack plug. Pulled 1" and perforated casing at 800' and 500'. Ran 1" back into 800' and spotted 15 sack plug. Pulled up to 500' and circulated cement to surface. Pulled 1" and topped well off. A total of 195 sacks of cement were used to this well.

Perfs:

Top	Bot	Thru	Comments
1360	1392		

RECEIVED
KCC DIST # 3
DEC 15 2016
CHANUTE, KS

DS
KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)

INVOICED
JAN 03 2017