

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-04421-00-00  
Spot: SENWNESE Sec/Twnshp/Rge: 3-17S-11W  
1980 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BURMEISTER NORTH Well #: 5  
County: BARTON Total Vertical Depth: 3314 feet

Operator License No.: 6239  
Op Name: ZINSZER OIL CO., INC.  
Address: PO BOX 211  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3304		100 SX
SURF	8.625	314		102 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2016 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PERRY HENMAN Company: ZINSZER OIL CO., INC. Phone: (785) 625-9448

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement.  
Packer stuck in well at 2700'. Bad casing above packer

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tubing connected to packer. Tied to tubing and pumped 40 sx cement. Disconnected from packer and pulled on joint of tubing. Pumped 20 sx cement. Pulled tubing and ran in with perf gun. Perforated at 1350', 715' and 625'. Ran tubing to 2370', tagged cement and pumped 70 sx cement. Pulled tubing to 1350' and pumped 45 sx cement. Pulled tubing to 720' and circulated cement to surface with 50 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 60 sx cement.

Perfs:

Top	Bot	Thru	Comments
3304	3314		
2850	3216		

KCC WICHITA  
DEC 19 2016  
RECEIVED

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed

Bruce Rodie  
(TECHNICIAN)

CJM

DEC 02 2016

INVOICED

Form CP-2/3

JAN 03 2017