

X
4-010299

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-23,771 -00-00

SE SW SW _____ / 4 SEC. 18, 16 S, 13 W
330 feet from S section line
4290 feet from E section line

Operator license# 4173 Lease: Luerman Well # 6
Operator: Col-Kan Development, Inc. County: Barton
Address: Box 89 Well total depth 3398 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 618 feet

Aband. oil well Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 22 Month: September Year: 1997

Plugging proposal received from: Kent

Company: D.S. & W. Well Service Phone: -

Were: Same as below.
Prospect Oil & Gas plugged this well for Col-Kan Development.
D.S. & W. Well Service performed the plugging operation.

Plugging Proposal Received by: Harb Daines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:00 P.M., Day: 22, Month: September, Year: 1997

Actual plugging report: Sanded to 3280' and dumped 5 sxs. Cut off pipe at 1822'. Pulled to 1550' and pumped 110 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled to 925' and pumped 40 sxs with 100# hulls. Pulled to 625' and pumped 30 sxs with 100# hulls. Pulled to 200' and circulate with 50 sxs.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____
Plugged through TUBING _____, CASING Elevation: _____ GL

I did[] / did not[] observe the plugging.

Chris Martin
(agent)

Form CP-2/3