

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21770-00-00
Spot: SWSW Sec/Twnshp/Rge: 34-30S-10W
660 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: ANTHONY Well Number: A1
County: KINGMAN Total Vertical Depth: 4546 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 255 165 SX
Production: Size 4.5 feet: 4538 100 SX
Liner: Size _____ feet: _____

8147.75

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/20/2002 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 243-4293

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 02/20/2002 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perf were covered w/sand from 4511'-4297 and capped w/4sxs of cement. The casing was recovered and pulled to 1600' where 35sxs of cement was spotted. The casing was pulled to 1100' where 35sxs of cement was spotted. The casing was pulled to 300' where cement was circulated. The remaining casing was pulled and cement topped off.


RECEIVED
KCC DISTRICT #2
FEB 27 2002
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

DATE 3-04-02

INV. NO. 2002061436