

2 100298

1-29-88 15.155.00146-0001240 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 10-31-77

SW SW NW, SEC. 21, T. 22 S, R. 7 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5483

Operator: Brown Operating Company

Name & Address 1000 Madison Street

Nickerson, KS 67561

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

Lease Name McVay Well # 1

County Reno 115.28

Well Total Depth 3547 feet

Conductor Pipe: Size 4 1/2" feet 3547

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas

Company to plug at: Hour: 2:30 Day: 29 Month: 1 Year: 19 88

Plugging proposal received from Doug

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: Sand to 3400' and dump 4 sxs cement. Shoot and pull 4 1/2". Set bridge @400'-380'.

Fill with redimix to surface

Plugging Proposal Received by J. L. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:00pm Day: 29 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT Sanded well to 3380' and dumped 4 sxs cement by bailer. Shot pipe off @3100' and pulled 4 1/2". Built bridge @500'; dumped 8 yards redimix to surface.

Remarks: Gravel & Concrete, Inc. #881  
(If additional description is necessary, use BACK of this form.)

INVOICED did not observe this plugging.

DATE 2-10-88  
INV. NO. 19802 WK

FEB 8 1988

Signed Johnny L Sanders (TECHNICIAN)

2-8-88