

To: 6 070578
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Feb. - 46
API NUMBER 15-167-07215-0000
SW NE SE, SEC. 2, T 14 S, R 15 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033
Operator: Murfin Drilling Co.
Name & Address: 250 N. Water # 300
Wichita, Ks. 67202
Larry M. Jack

feet from S section line
feet from E section line
Lease Name Sullivan Well # 5
County Russell 107.77
Well Total Depth 3316 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 924

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: 1:00 PM Day: 31 Month: July Year: 19 87

Plugging proposal received from Bill Brown

(company name) Murfin Drilling Co. (Russell) (phone) 316-267-3241

were: 8 5/8" - 924 ft. S.P. cuc with 230 sx, 5 1/2" csg set at 3312 w/75 sx cmt.

5 1/2" csg. squeezed at 30 ft w/150 sx cmt, at 400 ft w/150 sx cmt, and at

1550 ft. w/75 sx cmt, plug back 3112, no pipe recovery, proposal 200 sx 65/35

pozmix 10% gel - w/5 sx hulls. Pump in with pump truck.

Annulus was full of cement - visible at surface, also load and pressure

5 1/2" csg with cement. Plugging Proposal Received by MJS

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:00 PM Day: 31 Month: July Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sx 65/35 pozmix 10% gel and 5 sx hulls. (Annulus

full of cement due to squeeze) Pumped in 5 1/2" csg with 10 sx cement, 4 sx hulls, and

190 sx cement with 1 sx hulls mixed in. Max Pressure 500 PSIG. Shut in at 50 PSIG.

Cemented by Allied Cementing.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1987

8-18-87

Remarks: 8-5-87 (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Marion J. Schmidt (TECHNICIAN)

DATE 8-18-87

INV. NO. 17865