

4-042022

9-9

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-167-20,577-0000  
60'E.of  
NW SE NE /4 SEC. 02, 14 S, 15 W  
3630 feet from S section line  
930 feet from E section line

Operator license# 5259

Lease: Johnson "Twin" Well # 6

Operator: Mai Oil Operations

County: Russell

Address: P.O. Box 33  
Russell, Kansas 67665

Well total depth 3306 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 222 Feet  
W/150 sxs.cmt.

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License# 10745

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 9 Month: September Year 1999

Plugging proposal received from: Allen Bangert

Company: Mai Oil Operations Phone: -

Were: Ordered 280 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls.  
5 1/2" casing set at 3305' w/300 sxs cement. Perfs at 3126' - 3132'.  
Perf salt at 1525'. Anhy at 930'.  
Holes in casing at Cedar Hills and Dakota.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:45 A.M., Day 9, Month: September, Year: 1999

Actual plugging report: Ran in hole with tubing to 1535' - spotted 160 sxs cement with 400# hulls to circulate cement at surface. POOH with tubing and squeezed casing to 350# with additional 25 sxs cement. R.U. Cementers to 8 5/8" S.P. Squeezed 20 sxs cement down annulus - pressured-up to 300# - 400#. Blew out poor boy weld on casing. Plugging complete.

Remarks:     

Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING X CASING     . Elevation:      G.L.     

I did[ X ] / did not[      ] observe the plugging.

**INVOICED**  
DATE 9-24-99  
WIC. NO. 2000083

Dennis L. Hamel  
RECEIVED (agent)  
STATE CORPORATION COMMISSION Form CP-2/3  
SEP 20 1999  
CONSERVATION DIVISION  
Wichita Kansas  
9-20-99 (R)