

2 040521

12-29

44 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,165 - 0000

SE SW, SEC. 35, T 30 S, R 10W WE

3300 feet from S section line

660 feet from E section line

Lease Name ^{155e} Morsey Well # 1

County Kingman 150.18

Well Total Depth 4621 feet

Conductor Pipe: Size 8-5/8 feet 249

Surface Casing: Size feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Operator: Graves Drilling Company

Name & Address 151 N. Main, #850

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corp License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Elmo Morganstene

(company name) Clarke Corp (phone)

were: Sand to 4400' & 4 sx - 4-1/2" @ 4544' - 50' cmt plug @ 1600' - 50' cmt - plug @ 1100' - circ. from 300' - perms 4455'-4465'

MAILED

RECEIVED

1-10-90

JAN 10 1990

JAN 10 1990

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received By

Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 13:30 Day: 29 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT The perforations were covered w/sand to a top of 4400' & capped w/4 sx cmt - the 4-1/2" was shot loose @ 2500' and pulled to 1600' where a 50' cmt plug was spotted thru the 4-1/2" casing - 4-1/2" was pulled to 1100' where another 50' cmt plug was spotted - 4-1/2" was again pulled to 300' and cmt was circ to surface.

Remarks: B.J. Titan 60/40 poz 2% gel
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 23 1990

INV. NO. 27069

Signed [Signature]
(TECHNICIAN)