



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. H. E. Herbel of West Supply Co., Inc. has this date requested permission to plug the following described well:

Mr. H. L. Herbel guarantees payment of the plugging fee.

Operator's full Name: West Supply Company, Inc.

Complete Address: Box 327, Chase, Kansas

Lease Name: Community Selma Seyfert Well No. "C" # 3

Location: NW NW NW Sec. 28 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3368 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Walter Voth was instructed to plug the well as follows:

10 3/4" 120' Gwc.

Sanded hole back to 3340' & dumped 5 sax cement wh/dump
bailer. Pulled pipe to 350': circulated hole wh/mud; dis-
placed 25 sax cement thru pipe @ 300': Pulled pipe to 120';
displaced 20 sax cement thru pipe with mud pump. Pulled
remaining pipe, set rock bridge @ 20', & displaced 10 sax
cement, cementing to base of cell.
 Very truly yours,

Don Truman
 Conservation Division Agent