

State of Kansas



15-009-21224-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Sears of B & N Drilling Co. has this
date requested permission to plug the following described well:

Mr. Sears guarantees payment of the plugging fee.

Operator's full Name: Petroleum Energy Inc.

Complete Address: 710 One-Twenty-Bldg. Wichita, Kansas 67202

Lease Name: Rous Well No. 1

Location: 140' E of C W/2 E/2 SW Sec 28 Twp. 16 Rge. 11 (E)(W) X

County: Barton Total Depth 3355 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sears was instructed to plug the well as follows:

Fill hole with mud and spot 40 sx cement at 450'.

Fill hole with mud and spot 25 sx cement at 215'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.

2 sx cement in rat hole.

215' of 8 5/8" surface casing cement circ.

Very truly yours,

Duane Rankin
Conservation Division Agent