

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 3 1963

CONSERVATION DIVISION  
 Wichita, Kansas

10-3-63

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. W. R. Dodson of Halliburton Oil Producing has this  
 date requested permission to plug the following described well:

Mr. Dodson guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Co.

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name: Curtiss Well No. # 1

Location: E/2 NE SE Sec. 28 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3710 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dodson was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with mud to 240', 1st cementing plug, 1/4 sack hulls,

cement with 25 sacks. Fill hole with mud to 40', 2nd cement-

ing plug, 1/4 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent