

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter, Inc. has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Wendtlandt Well No. # 2

Location: SW SE S E Sec. 29 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3342 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

No surface pipe. Old cable hole.

Set bottom plug @ 2900' & dumped 5 sax cement with dump

bailer. Pulled pipe; run 2" tubing to 300'; circulated hole

with mud; displaced 50 sax cement thru tubing. Pulled

tubing to 60' & displaced 50 sax cement thru tubing with
pump truck, cementing to base of cellar.

Very truly yours,

Bob Luman
Well Plugging Supervisor