

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 300 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morten Specter of Morgenstern & Specter, Inc. has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: J. L. Wendlandt Well No. # 1

Location: C NE SE Sec. 29 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3348 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

10 3/4" 276' Cwc.

Set bottom plug @ 3000' & dumped 5 sx cement wh/dump bailer.
Pulled pipe to 300'; circulated hole wh/mud; displaced 30 sx
cement thru pipe wh/pump truck. Pulled remaining pipe. Set
rock bridge @ 40'; displaced 15 sx cement, cementing to base
of cellar.

Very truly yours,

Lawson
 Conservation Division Agent