



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Wolfe of Louis M. Mai has this
date requested permission to plug the following described well:

Mr. Louis M. Mai guarantees payment of the plugging fee.

Operator's full Name: Louis M. Mai

Complete Address: Box 33, Russell, Kansas 67665

Lease Name: Crawford "A" Well No. # 13

Location: SW NE SW Sec. 2 Twp. 14 Rge. 15 (E)(W) W

County: Russell Total Depth 3304 Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

12 1/2" csg. 925'.

Sanded hole back to 3275' & displaced 6 sax cement with dump bailer. No
pipe recovery. Set plug @ 900'. Squeezed ~~was~~ 7" csg. with 35 sax mud,
7 sax hulls, 85 sax cement, 15 sax mud, 3 sax hulls, & 15 sax cement.
Squeezed 12 1/2" csg. with 100 sax cement with Halliburton Cementing
Company's pump truck, cementing to base of cellar. Displaced 6 yds.
Ready-mix Cement outside 12 1/2" csg. cementing to base of cellar.
Cement traveled down hole 250' inside csg., displaced 8 yds. Ready-mix
Cement, cementing from 250' to base of cellar.

Very truly yours,

Joseph L. ...
Conservation Division Agent