

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1977

6-22-77

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,469-0000 (of this well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Drlg. & Sterling Drlg.

Complete Address 800 Bitting Bldg., Wichita, Kansas

Lease Name _____ Ward _____ Well No. 1

Location SW SW SE Sec. 20 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 4150'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor Sterling Drlg.

Address Sterling, Kansas License No. _____

Operation Completed: Hour 4 P Day 21 Month 6 Year 1977

The above well was plugged as follows:

RTD 4150' 8 5/8 csg set 700' cwc 435 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 40 sk cmt plug at 420' thru drill pipe.

Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 6-22-77

NO. 5371-W