

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1964

CONSERVATION DIVISION
Wichita, Kansas

1-24-1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Wendtlandt Well No. # 2

Location SW SE SE Sec. 29 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3342

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch's Gasing Pulling

Address: R. R. #4, Great Bend, Kansas License No. 457

Operation Completed: Hour 5 PM Day 20 Month 1 Year 1964

The Above well was plugged as follows:

No surface pipe. Old cable hole.

Set bottom plug @ 2900' & dumped 5 sax cement with dump bailer. Pulled
pipe; run 2" tubing to 300'; circulated hole with mud; displaced 50 sax
cement thru tubing. Pulled tubing to 60' & displaced 50 sax cement thru
tubing with pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Law Truman*
Well Plugging Supervisor

DATE 1/28/64

INV. NO. 8528-W