

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 13 1964

4-13-64  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Cook of Imperial Oil Of Kansas Inc. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Of Kansas Inc.

Complete Address: 780, Fourth National Bldg. Wichita, Kansas

Lease Name: Schaffer Well No. 1

Location: C NW NW Sec. 36 Twp. 22 Rge. (E) (W) 22

County Hodgeman Total Depth 1770' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

8 5/8"-275' Circulated w/cement.

Mud 1770' to 700' Snotted 25 Sax. cement 700' to 625'

Mud 625' to 275' Snotted 25 Sax. cement 275' to 200'

Mud 200' to 45' Plug, Halls, 15 Sax. cement 45' to 0

Very truly yours,

*J. P. Roberts*  
 Conservation Division Agent