



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Gene Smith of Kelso Casing Plugging has this date requested permission to plug the following described well:

Operator's Full Name: C & G Drilling

Complete Address: PO Box 158, Garfield Kans.

Lease Name: Wehester Well No. 1

Location: C. NE. NE. Sec. 36 Twp. 22 Rge. 22 (E) (S)

County: Hodgeman Total Depth: 4601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: Drilled never produced.

Mr. Smith was instructed to plug the well as follows:

There was 345' of 8/8 surface casing. C.C.
4 1/2 was set to 4600' plug back to 4440'
perforations were 4382-4381. 1st plug on bottom
with 35 lbs cement. 2nd plug at 900' with 50
lbs cement. 3rd plug at 360' with 35 lbs cement
4th plug at 40-0 with 10 lbs cement.

Very truly yours,

3-9-81

MAR - 9 1981

Lawrence Thomas
Conservation Division Agent