

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill;
filed August 18, 1967

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1967
CONSERVATION DIVISION

Dear Sir:

Mr. Dale Buller of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas 67202

Lease Name: Figge Well No. # 1

Location: C NE NE Sec. 11 Twp. 30 Rge. 10 (E)(W) W

County Kingman Total Depth 2570' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:

265' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 8
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.
These plugging orders were given by Howard Hess, Winfield, Ks.

Very truly yours,
Archie Elving
Conservation Division Agent