

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1964

CONSERVATION DIVISION
Wichita, Kansas

1-14-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Frank Starns of Sunray DX Oil Co. has this

date requested permission to plug the following described well:

Mr. Starns guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Co.

Complete Address: 312 W. Douglas, Wichita, Kansas

Lease Name: Roy Morisse Unit Well No. # 1

Location: NW NW SE Sec. 14 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4717 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Starns was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with mud to 250', 1st cementing plug, bridge

with hulls, cement with 25 sacks. Fill hole with mud to

40', 2nd cementing plug, bridge with hulls, cement with

10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent