

15-185-20044-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS-67202

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1967

7-31-67

CONSERVATION DIVISION
WICHITA, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed July 13, 1967.

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this
date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas 67530

Lease Name: Shepherd Well No. # 1

Location: NW SW SW Sec. 15 Twp. 22 Rge. 11 (E)(W) W

County Stafford Total Depth 3591' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

248' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Cliving
Conservation Division Agent