

State of Kansas



15-083-20470-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1976

CONSERVATION DIVISION
Wichita, Kansas

5-11-76

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Engle of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Engle guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 120 Bldg., Wichita, Ks.

Lease Name: Hastings "A" Well No. 1

Location: C NE SW Sec. 2 Twp. 22 Rge. (E)(W) 24

County: Hodgeman Total Depth 4770' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Engle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 660' thru drill

pipe. Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Law Massey