



15-159-30181-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 22, 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. Joe Cain of German Drilling Co. has this

date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc.

Complete Address: P.O. Box 797, Great Bend, Kansas

Lease Name: Harper Well No. 1

Location: C SW NW Sec. 2 Twp. 22 Rge. 8 (E) (W) X

County Rice Total Depth 3430' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

Fill hole with mud to 190'. Push plug and 1/2 sack hulls to 190' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent