

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Webb Hill of Mack Oil Co. has this

date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: Holle Well No. # 1

Location: C NE NW Sec. 19 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4883 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

277' of 8 5/8" surface pipe cement circulated with 225 sacks.
Fill hole with mud to 240', 1st cementing plug, 1/2 sack hulls,
cement with 20 sacks. Fill hole with mud to 40', 2nd cement-
ing plug, 1/2 sack hulls, cement with 10 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Ardie Elving
 Conservation Division Agent