

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

4-25-66

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Web Hill of Mack Oil Company has this  
date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Comapny

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: Hudson Well No. # 1

Location: C SE SE Sec. 21 Twp. 30 Rge. 10 (E)(W) W

County Kingman Total Depth 4747' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated with 190 sacks. Fill  
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sacks  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving  
Conservation Division Agent