

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26703-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 16-33S-9E
693 feet from S Section Line, 4823 feet from E Section Line
Lease Name: GREEN Well #: C-2
County: CHAUTAUQUA Total Vertical Depth: 2390 feet

Operator License No.: 33739
Op Name: SEK ENERGY, LLC
Address: 149 BENEDICT RD PO BOX 55
BENEDICT, KS 66714

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2262		
PROD	4.5	2390		280 SX
SURF	8.625	40		18 SX
T1	2.375	2260		

Well Type: SWD UIC Docket No: D28660.0 Date/Time to Plug:
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: DOUG FEWINS Company: Phone: (620) 363-0594

Proposed Plugging Method: Run cementing work string of tubing to TD and pump gel sufficient for gel spacers between cement plugs. Mix and pump cement to provide a 50' cement plug at TD. Pull cement work string up to 1000' and pump another 50' cement plug. Pull cement work string up to 550' and pump cement until cement is circulated to surface for a solid cement plug from 550' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 10/18/2016 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2300' gelled hole and spotted 10 sack plug. Pulled up to 1200' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. A total of 71 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2341	2346		
2303	2307		

RECEIVED
KCC DIST # 3
DEC 13 2016
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT
Plugged through: TBG

District: 03 Signed [Signature] (TECHNICIAN)

KCC WICHITA

DEC 16 2016
RECEIVED

12-16-16

INVOICED
JAN 03 2017