

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-21522-00-00  
Spot: SENE Sec/Twnshp/Rge: 20-19S-9W  
990 feet from N Section Line, 330 feet from E Section Line  
Lease Name: HABIGER B Well #: 1  
County: RICE Total Vertical Depth: 3246 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3241		140 SX
SURF	8.625	238		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: \_\_\_\_\_ Phone: (316) 524-1225

Proposed Plugging Method: According to the rules and regulations of the KCC. Note - Additional cement in well 10-20-2010 Circulate 50 sax cement from 403' to surface. 10-2-2014 110 sax @ 835' 10-9-2014 250 sax @ 835' 10-15-2014 200 sax @ 800' 10-17-2014 450 sax @ 800'

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/19/2016 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ck bottom. Cement squeezed on backside in 2014 at 835'-800' & in 2010 at 403' to surface. Set CIBP at 3190' and cap with 2 sx's cement. Perforate at 1200' and 290'. Run tubing at 1200' and pump 35 sx's common cement. Pull tubing to 800' and wait 1 hr. Tag cement at 1150'. Pump 35 sx's at 800', pull tubing to 290' and circulate cement to surface. Pull tubing out and top off.

Perfs:

Top	Bot	Thru	Comments
3236	3240		

Remarks: COPELAND CEMENT # 44419. GRESSELL PERF TICKET #1468.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

Form CP-2/3

INVOICED  
JAN 03 2017