

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22751-00-01
Spot: SESWNW **Sec/Twnshp/Rge:** 10-27S-13E
2749 feet from S Section Line, 4335 feet from E Section Line
Lease Name: KESTER **Well #:** 15
County: GREENWOOD **Total Vertical Depth:** 1250 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	4.5	1240		200 SX
SURF	7	43		10 SX
T1	2.375	1250		

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 12/14/2016 12:00 PM
Plug Co. License No.: 99973 **Plug Co. Name:** ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: MATT OSBORN **Company:** **Phone:** (620) 583-5527

Proposed Plugging Method: In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: MICHAEL HEFFERN **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2016 3:00 PM **KCC Agent:** MICHAEL HEFFERN

Actual Plugging Report:

pumped 15 sxs cement @ 1200, pulled tubing to 600', pumped 5 sxs cement, pulled tubing to 250', pumped 20 sxs cement to surface. gel spacers between cement plugs.

Perfs:

<u>Top</u>	<u>Bot</u>	<u>Thru</u>	<u>Comments</u>
1185	1195		

RECEIVED
KCC DIST # 3
DEC 19 2016
CHANUTE, KS
MH
KCC WICHITA

DEC 22 2016

RECEIVED

12-22-16

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED

JAN 03 2017

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-073-22751 0001
Cement or Acid Field Report
 Ticket No. **3087**
 Foreman Kevin McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
12-14-16	1031	Kester # 15	10	27	13	6W	Ks	
Customer <u>DAYSTAR Petroleum inc.</u>			Safety Meeting <u>KM</u> <u>RL</u> <u>AB</u> <u>DS</u>		Unit #	Driver	Unit #	Driver
Mailing Address <u>522 N. MAIN</u>					<u>102</u>	<u>RICK L.</u>		
City <u>EUREKA</u>			State <u>Ks</u>		<u>110</u>	<u>ALLEN B.</u>		
Zip Code <u>67045</u>					<u>145</u>	<u>DAVE G.</u>		

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing 2"
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: Rig up to 2" Reg. Tubing, Spot Cement Plugs AS Following inside 4 1/2 casing.

15 SKS @ 1200'
5 SKS @ 600'
20 SKS From 250' to SURFACE

KCC WICHITA
DEC 22 2016
RECEIVED

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge <u>2ND well 2</u>	450.00	450.00
C 107	0	Mileage	0	N/C
C 203	40 SKS	60/40 Pozmix Cement	12.75	510.00
C 206	150 *	Gel 4%	.20 *	30.00
C 108A	1.72 TONS	Ton Mileage	N/C	200.00
C 113	1.5 HRS	80 BBL VAC TRUCK	85.00	127.50
<u>THANK YOU</u>				
<u>M</u>				
			7.5%	
			Sub Total	1317.50
			Sales Tax	98.81
Authorization <u>Witnessed By Jason</u> Title _____			Total	1416.31

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.