

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-22876-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 10-27S-13E  
1625 feet from S Section Line, 3428 feet from E Section Line  
Lease Name: KESTER Well #: 23  
County: GREENWOOD Total Vertical Depth: 1267 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1265		175 SX
SURF	7	41		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2016 10:00 AM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: MATT OSBORN Company: \_\_\_\_\_ Phone: (620) 583-5527

Proposed Plugging Method: In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/14/2016 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1197', pumped 15 sxs cement, pulled tubing to 600', pumped 5 sxs cement, pulled tubing to 250', pumped 20 sxs cement to surface, gel, spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1215	1225		

RECEIVED  
KCC DIST #3  
DEC 19 2016  
CHANUTE, KS

MH

KCC WICHITA  
DEC 22 2016

RECEIVED  
12-22-16

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

INVOICED

JAN 03 2017

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-207 22876-00 00

Cement or Acid Field Report  
 Ticket No. **3058**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-14-16	1031	Kestor #23	10	27	13	GW	Ks
Customer Daystar Petroleum INC.			Unit #	Driver		Unit #	Driver
Mailing Address 522 N. MAIN			102	Rick L.			
City EUREKA			110	Allen B.			
State Ks			145	Dave G.			
Zip Code 67045							

Job Type P.T.A. Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 1"  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting: RAN 1" Hydrill Tubing inside 4 1/2 casing to 1197' Spot Cement  
Plugs AS Following:  
15 SKS @ 1197'  
5 SKS @ 600'  
20 SKS From 250' to SURFACE

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge 1 <sup>st</sup> well of 2	450.00	450.00
C 107	0	Mileage	0	N/C
C 203	40 SKS	60/40 Pozmix Cement	12.75	510.00
C 206	150 *	Gel 4%	.20 *	30.00
C 108 A	1.72 TONS	TON Mileage	M/C	200.00
C 113	1.5 Hrs	80 BBL VAC TRUCK	85.00	127.50
<u>THANK You</u>				
<u>— M —</u>				
			7.5%	
			<u>Sub TOTAL</u>	1317.50
			Sales Tax	98.81
Authorization <u>Witnessed By Jason</u> Title _____			Total	1416.31

KCC WICHITA  
 DEC 22 2016  
 RECEIVED

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.