

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22785-00-00
Spot: E2SWSWSE Sec/Twnshp/Rge: 22-18S-10W
343 feet from S Section Line, 2084 feet from E Section Line
Lease Name: KK Well #: 1-22
County: RICE Total Vertical Depth: 3264 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3263		175 SX
SURF	13.375	375		360 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DALLAS PRESTON Company: _____ Phone: (620) 886-0612

Proposed Plugging Method: PER KCC DIRECTIONS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/13/2016 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, ck bottom. Sand perfs to 3110' and cap with 5 sx's cement. Cut casing at 1840' and pulled to 1250' and pump 50 sx's common cement with 3% CC. Pull casing to 900' and wait 1hr. Tagged cement at 1100' with swab bar. Pumped 50 sx's common cement with 3% CC at 900', pulled casing to 425' and circulated cement to surface. Pulled casing out and topped off.

Top	Bot	Thru	Comments
3171	3186		

Remarks: DENIED TA DUE TO HFLD. COPELAND CEMENT # C-44506.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
JAN 03 2017

Form CP-2/3