

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-22061-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 10-21S-11W  
4847 feet from S Section Line, 3586 feet from E Section Line  
Lease Name: SIFERS Well #: 1  
County: STAFFORD Total Vertical Depth: 3370 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3280		WITH 2 SX CMT
PROD	5.5	3369	0	WITH 150 SX CMT
SURF	8.625	297		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2016 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3280' WITH 2 SX CMT. TEST CASING TO 400 PSI. PERFORATE AT 600' WITH 50 SX CMT (200# HULLS IN LAST 25 SX). PERFORATE AT 330' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2016 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3280' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" CASING AT 600' & 300'. RUN TBG IN TO 600'. PUMP DOWN TBG & OUT PERFS AT 600' WITH 25 SX CMT. PUMP & DISPLACE 200# HULLS & 25 SX CMT TO PERFS AT 600'. PULL TBG UP TO 300'. PUMP DOWN TBG FILLING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FROM 300' TO SURFACE WITH 120 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3330	3338		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer  
SA (TECHNICIAN)

RECEIVED  
DEC 15 2016  
KCC DODGE CITY

*MP*

Form CP-2/3

INVOICED  
JAN 03 2017