

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21017-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 9-25S-5W
3326 feet from S Section Line, 4641 feet from E Section Line
Lease Name: C W HAINES Well #: 2
County: RENO Total Vertical Depth: 3599 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3599		200 SX
SURF	8.625	366		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 12/08/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3383' CAPPED WITH 5 SX CEMENT ON TOP. PERFORATED @ 750' AND 400'. TRIPPED TUBING INTO 750' SPOTTED 50 SX OF CLASS A CEMENT, WAITED 2 HOURS TAGGED @ 482', TRIPPED TUBING TO 400' CIRCULATED TO SURFACE WITH 325 SX CEMENT. CEMENT FELL BACK TO 36', USED 35 SX OF CEMENT TO RAISE CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3480	3484		

Remarks: COPELAND OUT OF GREAT BEND BROUGHT CEMENT.

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

JAN 03 2017