

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21687-00-00  
Spot: NENESW Sec/Twnshp/Rge: 16-29S-16W  
2290 feet from S Section Line, 2971 feet from E Section Line  
Lease Name: CROMER Well #: 1  
County: KIOWA Total Vertical Depth: 5080 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 100 S MAIN ST, STE 420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4645		WITH 2 SX CMT
PROD	5.5	4983	1518	WITH 150 SX CMT
SURF	10.75	286		WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2016 9:40 AM  
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC  
Proposal Rcvd. from: ROBIN BROWN Company: ROBIN BROWN CONSULTING Phone: (316) 546-4801

Proposed Plugging Method: SET CIBP @ 4644' WITH 2 SX CMT. PLUG AT 990' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 70 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2016 10:35 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4545' WITH 2 SX CMT. 1ST PLUG AT 972' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 322' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. GOOD CIRCULATION THROUGHOUT JOB. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4694	4714		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
DEC 27 2016  
KCC DODGE CITY

INVOICED

JAN 03 2017