

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-189-21151-00-01  
Spot: NENESWSW Sec/Twnshp/Rge: 20-31S-35W  
1250 feet from S Section Line, 4036 feet from E Section Line  
Lease Name: LEFFLER Well #: 3  
County: STEVENS Total Vertical Depth: 2910 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		792		
CIBP		2510		WITH 10 SX CMT
PROD	5.5	2910	0	WITH 250 SX CMT
SURF	8.625	757		WITH 365 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2016 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2510' WITH 10 SX CMT. PLUG AT 1770' WITH 80 SX CMT. POOH & WOC. TEST CASING TO 500 PSI. PERFORATE AT 790' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2016 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2510' WITH 10 SX CMT. 1ST PLUG AT 1900' WITH 90 SX CMT. WOC. WELL WOULDN'T PRESSURE TEST. SET CIBP @ 792' & PRESSURE WELL TO 500 PSI. HOLDING. PERFORATE AT 773' WITH 275 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2560	2794		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

  
SA

(TECHNICIAN)

RECEIVED  
DEC 28 2016  
KCC DODGE CITY



INVOICED

JAN 03 2017

Form CP-2/3