

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22197-00-00
Spot: S2SE Sec/Twnshp/Rge: 32-28S-15W
530 feet from S Section Line, 1150 feet from E Section Line
Lease Name: JOHNSON Well #: 1-32
County: PRATT Total Vertical Depth: 4900 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN ST, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	4.5	4898	1524	WITH 160 SX CMT
SURF	8.625	374		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2016 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: SET CIBP @ 4605' WITH 2 SX CMT. PLUG AT 60' WITH 20 SX CMT. PLUGA T 930' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2016 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4620' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 941' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 387' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4743	4755		
4655	4661		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
SA (TECHNICIAN)

RECEIVED
DEC 27 2016
KCC DODGE CITY

Form CP-2/3

INVOICED
JAN 03 2017