

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22337-00-00
Spot: NESESE Sec/Twnshp/Rge: 2-27S-14W
993 feet from S Section Line, 340 feet from E Section Line
Lease Name: THOMPSON Well #: 1-2
County: PRATT Total Vertical Depth: 4460 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3836		WITH 2 SX CMT
PROD	4.5	4459	2200	WITH 200 SX CMT
SURF	8.625	393		WITH 480 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2016 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 3836' WITH 2 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 425' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2016 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3836' & PUMP 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
1ST PLUG AT 920' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX
CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3886	3890		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

RECEIVED
DEC 27 2016
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

Form CP-2/3

INVOICED

JAN 03 2017