

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23322-00-00
Spot: SWSESE Sec/Twnshp/Rge: 9-13S-16W
350 feet from S Section Line, 1077 feet from E Section Line
Lease Name: WINDHOLZ B Well #: 2
County: ELLIS Total Vertical Depth: 3515 feet

Operator License No.: 34556
Op Name: MILKE, ROD DBA R & J OIL CO.
Address: 1321 CENTRAL
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3515		150 sx
SURF	8.625	253		160 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JUSTIN SCHECK Company: MILKE, ROD DBA R & J OIL CO. Phone: (785) 650-9969

Proposed Plugging Method: Sand pump and sandline stuck at 3030'. Casing leaks.
Ordered 425 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: LKC-3169' - 3383' OH

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2016 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

ELI shot holes at 1650', 1104' and 609'. Express Well Service ran in hole with tubing to 3000'. Global rigged to tubing and pumped 135 sx cement w/300 # hulls mixed in. Pulled tubing to 1650' and pumped 160 sx cement w/200 # hulls to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing and pumped 30 sx cement to pressure with 300 psi. Shut in pressure 165 psi. Rigged to 8 5/8' surface casing and pumped 25 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.93038 -099.09860

Perfs:


KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2777

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

cm

Form CP-2/3

DEC 09 2016

INVOICED
JAN 03 2017