

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21668-00-00
Spot: SWSENESE Sec/Twnshp/Rge: 23-29S-16W
1638 feet from S Section Line, 516 feet from E Section Line
Lease Name: PIESTER A Well #: 1
County: KIOWA Total Vertical Depth: 4995 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN ST, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	5.5	4932	1992	WITH 250 SX CMT
SURF	10.75	265		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2016 9:05 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Rcvd. from: ROBIN BROWN Company: ROBIN BROWN PUMPING Phone: (620) 546-4801

Proposed Plugging Method: CIBP @ 4580' WITH 2 SX CMT. PLUG AT 920' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 10:10 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4620' WITH 2 SX CMT ON TOP. 1ST PLUG AT 910' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 292' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. GOOD CIRCULATION THROUGHOUT JOB. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4638	4675		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
DEC 27 2016
KCC DODGE CITY

INVOICED
JAN 03 2017

Form CP-2/3