

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23289-00-00
Spot: SENVNE Sec/Twnshp/Rge: 35-9S-21W
1020 feet from N Section Line, 1760 feet from E Section Line
Lease Name: DEYOUNG Well #: 5
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 34278
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C
Address: 18529 WALTERS RD PO BOX 606
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3850		400 SX
SURF	8.625	1148		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2016 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JEREMY ULRICH Company: MIKE'S TESTING & SALVAGE, INC Phone: (785) 324-0502

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 5 sx gel and 400 # hulls.
Perforations: 3729' - 3733'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2016 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Sanded off perforations up to 3650' with sand and 5 sx cement on top of sand. Cut casing at 1836'. Pumped 5 sx gel followed by 50 sx cement w/100 # hulls. Pulled casing to 1200' and pumped 150 sx cement w/100 # hulls. Pulled casing to 600' and pumped 150 sx cement w/100 # hulls. Good circulation of cement. Pulled casing. Hole standing full.

GPS: 39.23170 -099.63017

Perfs:

Top	Bot	Thru	Comments
3729	3733		

DEC 21 2016

Remarks: QUALITY CEMENT TICKET # 3072

Plugged through: CSG

District: 04

Signed _____

KCC WICHITA

(TECHNICIAN)

CM

NOV 29 2016

RECEIVED

NOV 21 2016

Form CP-2/3
DEC 21 2016